

# Homestake DUSEL Facility Infrastructure


**Richard DiGennaro**

*Project Manager and Systems Engineer*


**Lawrence Berkeley  
National Laboratory**

## Presentation Topics:

- General Concepts for infrastructure planning at Homestake for the Initial Suite of Experiments
- Some examples of proposed development for Homestake DUSEL
- Overview of existing facility infrastructure
- Overview of roles and responsibilities for DUSEL Preconstruction Planning
- Systems Engineering Plans – Requirements Database



# Homestake DUSEL Campus Development




## Four primary campus locations for research:


1. Surface campus at Yates Complex
2. Near-surface campus at 300 Level
3. Mid-level campus at 4850 Level
4. Deep-level campus at 7400 Level

Infrastructure will be maintained for access to additional, selected levels for bio- and geo-sciences and for unique experiments that require specific or isolated sites.

# Homestake Long Section



# Homestake and Lead Aerial Photo



**Water Treatment Plant**

**Open Cut**

**Yates Shops**


**Yates Complex**

**Lead**

**Ross Complex**



**300L Portal**

# Surface Campus Development Plan



## Yates Clean Transfer Station

Research equipment wash facilities to transfer from transport shipping crates to clean Equipment Cars and Containers for conveyance to underground laboratories.



## Yates Assembly, Staging and Test Area

Clean room and assembly shop for post-shipment inspection and pre-assembly prior to transport to underground laboratories.


# Partial List - SDSTA Building Inventory

| SDSTA Building Inventory         |       |                                          |                    |             |                |                                    | 12/1/2004                  |
|----------------------------------|-------|------------------------------------------|--------------------|-------------|----------------|------------------------------------|----------------------------|
| Description                      | Group | Type of Renovation                       | Building Footprint |             |                | Number of Usable/Accessible Floors | Total Floor Area (sq. ft.) |
|                                  |       |                                          | Length (ft.)       | Width (ft.) | Area (sq. ft.) |                                    |                            |
| Yates Sawmill                    | Yates | Alterations and Upgrades for DUSEL       | 68                 | 44          | 2,992          | 1                                  | 2,992                      |
| Yates Safety and Dry             | Yates | Alterations and Upgrades for DUSEL       | Irregular          |             | 5,883          | 3                                  | 17,649                     |
| Yates Ramp and Lamp Room         | Yates | Alterations and Upgrades for DUSEL       | 24                 | 22          | 528            | 1                                  | 528                        |
| Yates Hoist and MG Set Rooms     | Yates | Alterations and Upgrades for DUSEL       | Irregular          |             | 16,130         | 1                                  | 16,130                     |
| Yates Headframe Bldg.            | Yates | Alterations and Upgrades for DUSEL       | Irregular          |             | 16,679         | 1                                  | 16,679                     |
| Yates Bosses Office              | Yates | Alterations and Upgrades for DUSEL       | 26                 | 22          | 572            | 1                                  | 572                        |
| Administration Office            | Yates | Alterations and Upgrades for DUSEL       | 88                 | 93          | 8,184          | 2                                  | 16,368                     |
| Shovel and Battery Repair Shop   | Shops | Alterations and Upgrades for DUSEL       | 48                 | 23          | 1,104          | 1                                  | 1,104                      |
| Paint Shop                       | Shops | Alterations and Upgrades for DUSEL       | 34                 | 21          | 714            | 1                                  | 714                        |
| Main Warehouse and Plumbers Shed | Shops | Alterations and Upgrades for DUSEL       | Irregular          |             | 6,393          | 4                                  | 25,572                     |
| Machine and Metal Fab Shop       | Shops | Alterations and Upgrades for DUSEL       | Irregular          |             | 25,036         | 1                                  | 25,036                     |
| Iron House                       | Shops | Alterations and Upgrades for DUSEL       | 98                 | 55          | 5,390          | 1                                  | 5,390                      |
| Foundry                          | Shops | Alterations and Upgrades for DUSEL       | Irregular          |             | 13,710         | 1                                  | 13,710                     |
| Bit Shop and Shop Yard           | Shops | Alterations and Upgrades for DUSEL       | 30                 | 15          | 450            | 1                                  | 450                        |
|                                  |       | Alterations and Upgrades for DUSEL Total |                    |             |                |                                    | 142,894                    |

# Surface Facilities and Near-surface campus at 300 Level



Over 100,000 ft<sup>2</sup> of existing space at the Yates Complex may be used for User Activities and Facility Management

Existing space at the Ross Complex may be used for construction, maintenance, and site services.




The Near-surface Campus at 300L can provide drive-in access to material and fabrication shops, rooms for Education and Outreach, and R&D laboratories.

# Campus Development Concepts at 4850 Level





# Lab Module Concept for Analysis and Feasibility Studies



Purpose-built laboratories modules and infrastructure will be developed to match specific experimental requirements.

# Preliminary Feasibility Studies for Excavation and Ground Support for Typical Lab Modules



| FORMATION         | LEVEL       | LOCATION   | BOLTING                     | SHOTCRETE                         |
|-------------------|-------------|------------|-----------------------------|-----------------------------------|
| Poorman Formation | 4850L       | Roof       | 5 m long bolts @ 2 m c/c    | 90 mm fibre reinforced shotcrete  |
|                   |             | Side Walls | 8 m long bolts @ 1.75 m c/c | 100 mm unreinforced shotcrete     |
|                   | 7400L/8000L | Roof       | 5 m long bolts @ 1.75 m c/c | 100 mm fibre reinforced shotcrete |
|                   |             | Side Walls | 8 m long bolts @ 1.5 m c/c  | 90 mm fibre reinforced shotcrete  |
| Yates Unit        | 4850L       | Roof       | 5 m long spot bolts         | none                              |
|                   |             | Side Walls | 4 m long bolts @ 2.5 m c/c  | none                              |
|                   | 7400L/8000L | Roof       | 5 m long bolts @ 2.5 m c/c  | none                              |
|                   |             | Side Walls | 4 m long bolts @ 2.25 m c/c | 50 mm unreinforced shotcrete      |

Preliminary Geotechnical Analyses were done to support the site selection and identify preliminary requirements for excavation and ground support requirements.

# Water Shield Facility Concept for Multiple Experiments

Two Water Tanks:


14m dia. x 10m high

Four Experiments in each tank:

2m dia. x 2m high

Electrical Racks

Offices and Shops




# Feasibility Studies to consider using the existing Davis Lab for early experiments:

Current Davis Cavity

Dimensions:


55ft x 30ft x 32ft high

4850L Access




4874L Secondary Access


# Davis Lab with proposed LUX and Mini-CLEAN Experiments




# Davis Lab alternate configuration with LUX experiment and Low Background Facility



# Concept studies for large cavity construction




**Concept studies and preliminary geotechnical analyses have demonstrated that large cavities of ~50 m diameter and 100 m height are feasible at 4850 Level and deeper.**




# Deep Campus at 7400 Level and access to additional ramps and drifts down to 8000 Level

**Phased development of purpose-built lab modules at 7400L will enable concurrent research operations with on-going excavation and construction.**




**Access to other levels will enable unique or exploratory research, including the existing Drilling Room at the 8000 Level**



# Proposed Surface and Underground Development Program

| <b>Homestake Interim Lab and DUSEL</b><br><b>Summary of Development of Space and Availability</b><br><br>(Underground space fully outfitted and ready for detector installation) |                 | Labs, Shops, Offices<br>Usable Floor Area |               | Excavation Volume<br>(including access drifts) |                |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|-------------------------------------------|---------------|------------------------------------------------|----------------|
|                                                                                                                                                                                  |                 | sq. ft.                                   | sq. m.        | cu. yd.                                        | cu. m.         |
| <b>4850 Level</b>                                                                                                                                                                | <b>Subtotal</b> | <b>107,351</b>                            | <b>9,973</b>  | <b>111,115</b>                                 | <b>84,903</b>  |
| Ross Shops for Construction Staging                                                                                                                                              |                 | 12,469                                    | 1,158         | 5,738                                          | 4,385          |
| Davis Lab, Sanford Lab, and Bio-Geo Lab                                                                                                                                          |                 | 15,738                                    | 1,462         | 13,543                                         | 10,348         |
| Lab Module #1 and Common Facilities                                                                                                                                              |                 | 26,464                                    | 2,459         | 25,155                                         | 19,221         |
| Lab Module #2                                                                                                                                                                    |                 | 17,560                                    | 1,631         | 21,433                                         | 16,377         |
| Lab Module #3                                                                                                                                                                    |                 | 17,560                                    | 1,631         | 23,121                                         | 17,667         |
| Lab Module #4 (excavation only, without lab outfitting)                                                                                                                          |                 | 17,560                                    | 1,631         | 22,125                                         | 16,906         |
| <b>7400 Level</b>                                                                                                                                                                | <b>Subtotal</b> | <b>63,588</b>                             | <b>5,907</b>  | <b>98,477</b>                                  | <b>75,246</b>  |
| Lab Module #1 and Common Facilities                                                                                                                                              |                 | 28,468                                    | 2,645         | 29,594                                         | 22,613         |
| Lab Modules #2 and #3 (excavation only, without lab outfitting)                                                                                                                  |                 | 35,120                                    | 3,263         | 68,883                                         | 52,633         |
| <b>300 Level</b>                                                                                                                                                                 | <b>Subtotal</b> | <b>8,668</b>                              | <b>805</b>    | <b>14,007</b>                                  | <b>10,703</b>  |
| Lab #1, Shops, and E&O Rooms                                                                                                                                                     |                 | 8,668                                     | 805           | 14,007                                         | 10,703         |
| <b>Surface</b>                                                                                                                                                                   | <b>Subtotal</b> | <b>98,000</b>                             | <b>9,104</b>  |                                                |                |
| DUSEL Offices and User Support Areas, Phase 1                                                                                                                                    |                 | 10,000                                    | 929           |                                                |                |
| Sanford Clean Room and Assembly Shop                                                                                                                                             |                 | 6,000                                     | 557           |                                                |                |
| DUSEL Offices and User Support Areas, Phase 2                                                                                                                                    |                 | 32,000                                    | 2,973         |                                                |                |
| Sanford Center for Science Education                                                                                                                                             |                 | 50,000                                    | 4,645         |                                                |                |
| <b>Total</b>                                                                                                                                                                     |                 | <b>277,607</b>                            | <b>25,790</b> | <b>223,599</b>                                 | <b>170,852</b> |



# Yates Shaft Upgrade Plan

Improved access to the 4850 Level for personnel, equipment, and utilities

## Existing Cage Dimensions and Capacities

### Yates Cage Hoist

Maximum cage dimensions:

1.4 x 3.7 x 2.2m high (side-by-side)  
(4' 8" x 12' 1.5" x 7' 2" high)

Maximum cage payload:

5,450 kg (12,000 lb), nominal  
5,900 kg (13,000 lb), at 1/2-speed.

### Ross Cage Hoist

Maximum cage dimensions:

1.3 x 3.8 x 2.2m high  
(4' 4-5/8" x 12' 5" x 7' 2" high)  
5,450 kg (12,000 lb), nominal  
6,100 kg (13,400 lb), at 1/2-speed.



### #6 Winze Cage Hoist

Maximum cage dimensions:


1.3 x 3.7 x 2.2m high (double deck)  
(4' 4" x 12' 1-1/2" x 2.2m high)

Maximum cage payload:


5,450 kg (12,000 lb), nominal  
6,400 kg (14,000 lb), at 1/2-speed.



# Homestake Facility Power Distribution




# General Plan for Primary Ventilation



Exhaust Fans at #5 Shaft (alternate or secondary exhaust at Oro Hondo)  
Intake via Yates and Ross Shafts

# Proposed R&D for Infrastructure Development

- **Hazardous Materials Transport, Storage, Operations**  
(e.g., Large volumes of cryogenics)
- **Clean Transport Containers and Handling Systems (similar to SNOLab configurations)**  
(Standard sizes, capacities, “Double-bagged”, clean room transitions, rigging and lifting fixtures, etc.)
- **Large-scale Reduced-radon Air Supply**
- **Large-scale Underground Clean Rooms and Clean Transitions**
- **Large-scale Purified Water Systems**
- **Site Investigations and Detailed Geotechnical Analyses**
- **U/G Communications, monitoring, IT, cyberinfrastructure**



# Institutional Responsibilities and Sub-project Teams

| Institution                                                                                                                                                | Sub-project Teams                                                                                                                                |
|------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|
| U.C. Berkeley,<br>Lawrence Berkeley National<br>Laboratory, South Dakota<br>School of Mines and Technology<br>and<br>Homestake Scientific<br>Collaboration | Science and Engineering Research Program<br>Development                                                                                          |
|                                                                                                                                                            | Environment, Health and Safety Oversight                                                                                                         |
|                                                                                                                                                            | Education and Outreach Program Development                                                                                                       |
| Lawrence Berkeley National<br>Laboratory                                                                                                                   | Project Management and Project Controls                                                                                                          |
|                                                                                                                                                            | Systems Engineering (requirements, risk and value<br>management; interfaces and systems integration;<br>validation)                              |
|                                                                                                                                                            | Underground Labs: Detailed engineering design and<br>coordination with research program requirements                                             |
|                                                                                                                                                            | Research Equipment and Experimental Instrumentation:<br>engineering and design support                                                           |
| South Dakota Science and<br>Technology Authority and South<br>Dakota School of Mines and<br>Technology                                                     | Environment, Health and Safety Management                                                                                                        |
|                                                                                                                                                            | Facility Management, Site Services and Site Operations                                                                                           |
|                                                                                                                                                            | Mining-to-Labs Conversion: Re-entry and infrastructure<br>rehabilitation                                                                         |
|                                                                                                                                                            | Underground Labs: Construction management,<br>commissioning, and installation of research<br>instrumentation                                     |
|                                                                                                                                                            | New excavation, underground facility infrastructure and<br>services construction management, inspection, quality<br>assurance, and commissioning |



## UNDERGROUND LABS and SPACE

Experiment or Program Name: \_\_\_\_\_  
Principal Investigator or Contact Person: \_\_\_\_\_  
Brief Summary: \_\_\_\_\_

*Note: General requirements and lab module infrastructure for physics and earth sciences experiments have been compiled for DUSEL planning (ref. [http://www.dusel.org/InfrastrMatrices\\_rev.xls](http://www.dusel.org/InfrastrMatrices_rev.xls)). As-needed, use this checklist to add, update, or modify information for the proposed experiment.*

### 1. Modules or Functional Uses:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

### 2. General Information:

Probable Start (year) \_\_\_\_\_  
Duration \_\_\_\_\_  
Space (Volume) L x W x H (m<sup>3</sup>) \_\_\_\_\_

Depth/Shielding (mwe) \_\_\_\_\_  
Occupancy (Peak/Avg) \_\_\_\_\_

### 3. Mechanical

Temperature  
\_\_\_ Uncontrolled  
\_\_\_ 20 +/- 5 deg. C (Air Cond.)  
\_\_\_ other: \_\_\_\_\_

\_\_\_ Compressed Air

### Cylinder Gases:

\_\_\_ Inert  
\_\_\_ Flammable  
\_\_\_ Toxic  
\_\_\_ Carbon Dioxide  
\_\_\_ Nitrogen Gas  
\_\_\_ Liquid Nitrogen  
\_\_\_ other: \_\_\_\_\_

### 4. Electrical

Approx. total power (kW)  
(Peak/Avg.) \_\_\_\_\_  
Other electrical needs (describe):  
\_\_\_\_\_

### 5. Chemicals:

Bases

Clean Room \_\_\_\_\_  
Storage \_\_\_\_\_

### 7. Special Facilities:

Material Access \_\_\_\_\_  
Access Schedule \_\_\_\_\_  
Cleanliness \_\_\_\_\_  
Security \_\_\_\_\_  
Data Communication: \_\_\_\_\_  
\_\_\_\_\_

### 8. Laboratory, Machine Tools, and Other Equipment:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## **SURFACE LABS and SPACE**

Experiment or Program Name: \_\_\_\_\_

Principal Investigator or Contact Person: \_\_\_\_\_

Brief Summary: \_\_\_\_\_

1. Rooms or Functional Uses:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

2. General Information:

Probable Start (year) \_\_\_\_\_

Duration \_\_\_\_\_

Space (Approx. Floor Area or  
Volume) \_\_\_\_\_

Occupancy (Peak/Avg) \_\_\_\_\_

3. Mechanical

Temperature

\_\_\_ Uncontrolled

\_\_\_ 20 +/- 5 deg. C (Air Cond.)

\_\_\_ other: \_\_\_\_\_

Humidity

\_\_\_ 50% +/- 20%

\_\_\_ Uncontrolled

\_\_\_ other: \_\_\_\_\_

Air Filtration/Recirculation

(describe): \_\_\_\_\_

Cylinder Gases:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4. Electrical

Approx. total power (kW)

(Peak/Avg.) \_\_\_\_\_

Other electrical needs (describe):

\_\_\_\_\_  
\_\_\_\_\_

5. Chemicals:

\_\_\_ Bases

\_\_\_ Acids

\_\_\_ Solvents

\_\_\_ Radioisotopes

\_\_\_ Chemical inventory storage

\_\_\_ Chemical waste storage

\_\_\_ Biological storage

\_\_\_ Radioisotope storage

\_\_\_ Cryogenics

\_\_\_ Hazardous/Special Handling:

\_\_\_\_\_

7. Special Facilities:

Material Access \_\_\_\_\_

Access Schedule \_\_\_\_\_

Cleanliness \_\_\_\_\_

Security \_\_\_\_\_

Crane Access: \_\_\_\_\_

Data Communication: \_\_\_\_\_

\_\_\_\_\_

8. Laboratory, Machine Tools, and  
Other Equipment:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

9. Other Needs or Requests:

# Systems Engineering - Requirements Management Database

**Requirement Number ID:** A unique serial number identifier for each record.

**Work Breakdown Structure:** WBS # reference for project controls and review.

**Organization:** Institution, user group, or experiment representing the origin for the defined need or constraint.

**Owner:** Named individual who is responsible throughout the project design and execution process to verify that the requirement is achieved or to identify and report deviations.

**System:** Top-level grouping for an experiment, common facility, institutional program, or regulatory agency.

**Sub-system:** Mid-level grouping by elements within each system.

**Topic:** Lowest-level grouping by engineering discipline or project management categories.

**Requirement Statement:** Concise, summary definition of functional objectives (what the system must do) or performance objectives (how well it must be done).

**Rationale:** Optional supplementary information to further explain the requirement statement.

**Type:** Basis for the requirement, such as functional, performance, budgetary, regulatory, interface, etc.

**Source(s):** Examples: Funding or regulatory agencies (e.g., NSF, DOE, MSHA, OSHA, DENR, laws & statutes), Institutional (SDSTA, Homestake Lab, LBNL, Site-specific design criteria), Programmatic (Education & To-be-determined (TBD), Draft, Defined, Approved, Verified, Deleted, or Obsolete Outreach, Maintenance & Operations, Environment, Health, Safety & Security, Policies and Procedures), Users Experimental and Research (Functional, Performance, Analysis, Existing Conditions), Subcontracts and Industry Standards, Lessons Learned.

**URL Link(s):** Optional, additional reference information or detailed requirements documentation.

**Comments & Revision Note:** Optional descriptive narrative.

# Supplementary Slides

# Systems Engineering Toolkit

Objective: Implement a unified approach to Systems Engineering and Project Management

- Communication
- Requirements Management Database
- Continuous Risk Management
- Work Breakdown Structure, Subsystem Interface Management
- Integrated Safety Management
- Design-Reviews, Integration, and Performance Management
- Value Management
- Configuration Management and Change Control
- Project Controls: Earned Value Management System

# PROCESS: Homestake DUSEL

## Environment, Health & Safety and Project Execution Plan

### 1. Environment, Health and Safety and Integrated Safety Management

#### 1.1 Integrated Safety Management Plan

#### 1.2 Environmental Laws, Regulations, and Best Practice

##### 1.2.1 Regulatory Agencies and Jurisdiction

##### 1.2.2 Permitting, Codes, Standards and Regulatory Compliance

##### 1.2.3 Environmental Assessment and Environmental Impact Statement

##### 1.2.4 Environmental Monitoring Program

#### 1.3 Hazardous Material Management

#### 1.4 Regional communication and public information

#### 1.5 Emergency Management, Response and Communication

##### 1.5.1 Fire Prevention, Containment, and Monitoring

##### 1.5.2 Safeguards and Security

##### 1.5.3 Regional resources and cooperative agreements

( continued )

# PROCESS: Homestake DUSEL

## Environment, Health & Safety and Project Execution Plan

### 1. Environment, Health and Safety and Integrated Safety Management (cont.)

#### 1.6 Safety Training Programs and Oversight

- 1.6.1 Staff/Employees

- 1.6.2 Experimenters, Students, Visitors, and Guests

- 1.6.3 Contractors, consultants, services

#### 1.7 Safety Review Process, Inspection, Surveillance and Oversight

- 1.7.1 Construction

- 1.7.2 Experiments

- 1.7.3 Maintenance and Operations

#### 1.8 Recycling and Waste Disposal Plans

#### 1.9 Energy Conservation Performance and Energy Management

#### 1.10 Facility Life Cycle Plan, De-integration and Disposal (D&D)

- 1.10.1 Laboratory Closure Plan

# PROCESS: Homestake DUSEL Project Execution Plan

## **2. Project Execution Plan**

2.1 Research Objectives Summary

2.2 Preliminary Baseline Performance Key Parameters

2.3 Project Governance and Management Organizational Plan

2.3.1 Sub-awards and Organizational Responsibilities

2.4 Work Breakdown Structure (WBS)

2.4.1 WBS for MREFC Construction Project

2.4.2 WBS for Operations

2.4.3 WBS Dictionary

2.5 Project Resource-Loaded Schedule

2.5.1 Preconstruction Planning and Development

2.5.2 MREFC Construction

( Continued )

# PROCESS: Homestake DUSEL Project Execution Plan

## **2. Project Execution Plan** (continued)

### 2.6 Project R&D Plan

- 2.6.1 Preliminary Site Investigation: Coring and Geotechnical Analyses
- 2.6.2 Excavation methods and technologies
- 2.6.3 Feasibility studies for Large-span Cavities
- 2.6.4 Site-specific Safety Standards and Guidelines
- 2.6.5 Underground systems and controls for hazardous materials
- 2.6.6 Underground Communications, Cyberinfrastructure, IT, and monitoring systems
- 2.6.7 Large-scale Reduced-radon Air Supply
- 2.6.8 Large-scale underground clean rooms
- 2.6.9 Large-scale purified water systems

### 2.7 Internal and Institutional Project Oversight and Design Review Plan

### 2.8 Acquisition Plan and Project Delivery Methods

( Continued )

# PROCESS: Homestake DUSEL Project Execution Plan

## **2. Project Execution Plan** (continued)

### 2.9 Systems Engineering Plan

- 2.9.1 Requirements Management
- 2.9.2 Continuous Risk Management
- 2.9.3 Configuration Management
- 2.9.4 Quality Assurance and Quality Control
- 2.9.5 Value Management
- 2.9.6 Interface Control
- 2.9.7 Systems Integration, Testing, and Validation
- 2.9.8 Information, Communication and Document Management

### 2.10 Project Management Control System

- 2.10.1 Baseline Cost and Schedule Performance Parameters
- 2.10.2 Resource-loaded Project Schedule
- 2.10.3 Preliminary Risk Analysis and Risk Mitigation
- 2.10.4 Preliminary Cost Estimate and Contingency Analysis
- 2.10.5 Partnerships and Partnership Funding
- 2.10.6 Project Controls and Earned Value Management
- 2.10.7 Technical and Financial Oversight, Reporting, and Reviews
- 2.10.8 Change Control and Contingency Management
- 2.10.9 Project Staffing and Hiring Plan

# PROCESS: Homestake DUSEL Project Execution Plan


## **3. Summary: Technical Feasibility and Constructability**

## **4. Transition to Operations**

- 4.1 Operational Readiness Criteria
- 4.2 Commissioning
- 4.3 Conduct of Operations Plan
- 4.4 Operations Management Plan
- 4.5 Maintenance and Operations Plan


Estimated Cost  
\$K

**NSF Funding Profile: Pre-Construction Planning and DUSEL Project  
(incl. 3% annual escalation, with contingency, then-year-\$)**




Estimated Cost  
\$K

**Sub-Projects Cost Profile (excluding Experimental  
Research Equipment) (incl. 3% annual escalation, with Contingency)**



# Existing Drifts and Access for Campus Development at 4850 Level



# Existing Drifts and Access for Campus Development at 7400 Level

Yates Shaft Projected

